Bruhat Bangalore Mahanagara Palike

Executive Engineer Byatarayanapura Division

Name of Work: Supplying and Laying of various bituminous mixes for repair of potholes and Road cut Portions from established Hot Mix Plant of minimum 50/80 TPH capacity (In Fully working condition) including manufacturing, supplying and laying including the cost of all materials, machineries, labours, consumables etc complete for a period of 2 years in Byatarayanapura Division

Sl No	Description of Items	No	Unit	Rate	Amount
1	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading ll Material PWD CSR 21-22 VOl 3 it. No 10.5 Page No 76 (as per Issue Rates Dated 01-01-2023)				
		1	**Sqm**	**460.90**	**460.90**
	Approved Rates	460.90			
2	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with 40 mm of Wet Mix Macadam and Bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading ll Materialincluding all lead, lift and cost of materialsandlabouretc.,complete				
		1	**Sqm**	**415.72**	**415.72**
	Approved Rates	415.72			
3	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with 100 mm of Wet Mix Macadam and Bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading ll Material including all lead, lift and cost of materialsandlabouretc.,complete				
		1	**Sqm**	**561.99**	**561.99**
	Approved Rates	561.99			
	Total No of Wards	10			
	Total Amount Allocated for Each Ward				**150000.00**
	Total Amount Allocated for 10 Ward				**1500000.00**
	Rupees in words : Sixty Laksh (including 18% GST)				

Certificate

1. The Quantity should be Asseseed based on the BBMP Fix My Street Application App.
2. The workspot was inspected and works is found to be necessary.
3. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
4. The rates adopted based on the PWD SR,Bangalore circle for year 2021-2022, and Approved Rate.

ADMINISTRATIVE SANCTION
Accorded for Rs. 150.00 Lakhs
Head of A/c. P-3706
DTC Ref. No. 47 Date 26/12/23
AE/DM EE(BTP) BBMP

Executive Engineer
Byatarayanapura Division
BBMP